



Seismic Safety of Nonstructural Components and Systems in Medical Facilities

Gilberto Mosqueda
Assistant Professor
Department of Civil, Structural and Environmental Engineering
University at Buffalo



Research Collaborators

- Professor Andre Filiatrault
- Professor Andrei Reinhorn
- Rodrigo Retamales, PhD Candidate
- Ryan Davis, Graduate Student



Overview

- Definition and importance of nonstructural components and systems in seismic events
- Current code requirements
- UB Nonstructural Component Simulator (UB-NCS)
 - Capabilities and limitations of new testing apparatus dedicated for testing nonstructural components
- Proposed protocol for testing with UB-NCS
- Recent experiments of composite hospital room to examine seismic safety of medical equipment




Nonstructural Components

- Systems and elements in a building that are not part of the load-bearing structural system
- Architectural
 - Cladding, glazing
 - Ceilings, partition walls
- Mechanical and Electrical
 - Distribution systems - piping
 - HVAC ducts and equipment
- Contents
 - Free-standing and anchored medical equipment, computers, shelves, etc.



Investment in Nonstructural Components and Content



Role of Nonstructural Components in Earthquakes

- Hospital emergency room immediately after the 1994 Northridge earthquake



Role of Nonstructural Components in Earthquakes

- 2001 Nisqually Earthquake (Filiatrault)



Role of Nonstructural Components in Earthquakes

- In order for a building or facility to remain operational after an earthquake, both structural and nonstructural systems must remain intact
- In past earthquakes
 - many hospitals and other facilities have survived earthquakes without structural damage, but lost functionality due to nonstructural damage
 - 50% of \$18 Billion in building damage following 1994 Northridge earthquake was due to nonstructural damage (Kircher 2003)
- In addition to structural response, compatible seismic performance of nonstructural components is essential to achieve global performance objectives



Code Requirements (ASCE 7-05)

International Building Code references ASCE 7-05

Nonstructural design requirements depend on:

- Seismic Design Category of structure
 - A-F, depending on occupancy category and site spectral accelerations at short (S_{DS}) and long period (S_{D1})
- Occupancy Category of structure
 - I – low hazard to human life (storage)
 - II – regular buildings
 - III – high hazard to human life (schools, meeting rooms)
 - IV – essential facilities (hospitals, emergency response center)
- Nonstructural Importance Factor $I_p = 1$ or 1.5
 - $I_p = 1.5$ if component (a) is essential for life-safety; (b) contains hazardous materials; or (c) is required for functionality of Cat. IV structure



Code Requirements (ASCE 7-05)

- Equivalent Static Design Force

$$F_p = \frac{0.4a_p S_{DS} W_p}{R_p / I_p} \left(1 + 2 \frac{z}{h} \right)$$

- a_p = component amplification factor (1-2.5)
- I_p = component importance factor (1-1.5)
- R_p = component response modification factor (1-12)
- S_{DS} = short period spectral acceleration
- W_p = component weight
- z/h = normalized height of component in building





Code Requirements (ASCE 7-05)

- **Special Certification Requirements for Designated Seismic Systems** ($I_p = 1.5$ in Seismic Category C-F)
 - Active mechanical and electrical equipment that must remain operable following design earthquake shall be certified by supplier as operable
 - Components with hazardous contents shall be certified by supplier as maintaining containment
- Must be demonstrated by
 - Analysis
 - Testing (shake table testing using accepted protocol)
 - AC-156
 - Experience Data




Special Requirements for Hospitals in California

- SB-1953 Hospital Seismic Retrofit Program
 - Evaluate current hospital building stock
 - Meet nonstructural performance standards by 2002
 - Meet structural performance standards for collapse prevention by 2008 (possible extension to 2013)
 - Buildings capable of continued operation after design level event by 2030
- ASCE 7-05 Seismic Qualification Requirements apply for mechanical and electrical equipment



Testing protocols for experimental seismic qualification of equipment

- ICC-ES AC156 shake table testing protocol
 - Test under non-stationary random excitations matching target floor response spectrum




- Force levels consistent with static design force F_p
- Test unit should remain functional after testing




Testing protocols for seismic fragility assessment

- FEMA 461 testing protocols:
 - Racking (quasi-static) test for displacement (drift) sensitive nonstructural components
 - Shake table tests for acceleration sensitive components
- Objective is to determine mean loading conditions triggering different damage levels




Testing protocols for seismic fragility assessment

- FEMA 461 testing protocols
 - Racking protocol: low rate cyclic displacements and/or forces selected to match 'rainflow cycles' for expected seismic response of buildings



Testing protocols for seismic fragility assessment

- FEMA 461 testing protocols
 - Shake table protocol:
 - Simulated scaled floor motions to evaluate the response of acceleration sensitive systems (single attachment point)
 - Narrow-band random sweep acceleration matches spectra



Application of Testing Protocol

HVAC Equipment Mounted on
Vibration Isolation/Restraint Systems



PI: A. Filiatrault
Sponsor: MCEER/ASHRAE
Industry Partner: ASHRAE





University at Buffalo Nonstructural Component Simulator (UB-NCS)

Modular and versatile two-level platform for experimental seismic performance evaluation of full scale acceleration and displacement sensitive nonstructural components under realistic full scale floor motions



UB-NCS Geometry





UB-NCS Properties

- General properties
 - Capable of 2 horizontal DOF (+ 1 vertical when mounted on shaking table)
 - Max. specimen weight: 6 kips/level (27 kN/level)
 - Operating frequency range: up to 5.0 Hz
- Activated by 4 high performance dynamic actuators
 - Force per actuator: 22 kips (100 kN)
 - Peak displacement: ± 40 in (1 m)
 - Peak velocity: 100 in/s (2.5 m/s)
 - Peak acceleration: up to 3g's



UB-NCS Testing Capabilities

- Replicate recorded or simulated floor motions at upper levels of multi-story buildings
- Replicate full scale near-fault ground motions (including large displacement/velocity pulses)
- Capability to generate data required to better understand behavior of nonstructural components under realistic demands
 - Develop experimental fragility curves
 - Develop effective techniques to protect equipment in buildings



Performance Evaluation of UB-NCS

- Objectives:
 - Identify dynamic properties and limitations of UB-NCS
 - Evaluate system fidelity for replicating simulated and recorded full scale floor motions
- Extensive testing including:
 - Hammer impact and white noise tests
 - Sine sweep tests
 - Transient floor motions
 - New protocols under development




Performance Evaluation of UB-NCS

- UB-NCS dynamic properties limit frequency range of operation to 5 Hz


Dynamic property	Frequency (Hz)
Actuator vertical bow-string frequency	8.7-9.2
Actuator horizontal bow-string frequency	6.6
Actuator oil-column frequency	12.3-13.6
Frame transverse direction frequency	38.9-39.3
Platform dish mode frequency	19.1-20.0



Performance Evaluation of UB-NCS



- Tapered sinusoidal test examples




Testa11: $f=1$ Hz, $A=\pm 4$ in.




Performance Evaluation of UB-NCS

- Simulated seismic response of building
 - Existing medical facility in the San Fernando Valley, Southern California
 - 4-story steel framed building with non uniform distribution of mass and stiffness
 - Floor motions obtained from nonlinear numerical analysis
 - Synthetic ground motions with seismic hazard of 10%/50yrs




Performance Evaluation of UB-NCS

- Simulated building seismic response



Performance Evaluation of UB-NCS

- Simulated building seismic response
- Accuracy of test machine measured by comparing
 - Response spectrum
 - Interstory drift history



Performance Evaluation of UB-NCS

- Recorded building seismic response, 1992 Landers $M_w=7.4$
 - 52-story office building in LA
 - Concentrically braced steel frame core with outrigger moment frames




(CSMIP)





Performance Evaluation of UB-NCS

- Reproduction of recorded seismic response



Performance Evaluation of UB-NCS

- Applied iterative corrections to input in order to match
 - desired response spectrum
 - Interstory drift




UB-NCS Testing Protocol

- New protocol is being developed to
 - Simultaneously apply displacement and acceleration demands similar to those expected in real buildings
 - Test systems with multiple attachment points at different floor levels (e.g. piping systems) and sensitive to both displacements and accelerations
- Motions for bottoms and top level are determined for a given z/h ratio to match:
 - Target floor acceleration response spectrum
 - Inter-story drift spectrum



UB-NCS Testing Protocol

- Example Probabilistic Seismic Hazard with a probability of exceedance of 10% in 50 (USGS)



USGS Spectral Acceleration Amplitudes for a SH with PE 10%/50yrs

Period T (sec)	Spectral Amplitude (g)
0.0	0.63
0.1	1.22
0.2	1.51
0.3	1.34
0.5	0.96
1.0	0.50
2.0	0.22

← S_{DS}


← S_{DI}

3
3



UB-NCS Testing Protocol

- Power Spectral Density consistent with seismic hazards is used as input for building model
- Floor motion demands computed by considering shear-flexural model with secondary system
 - Primary system periods: $T_p=0.1-5$ sec
 - Secondary system periods: $T_s=0-5$ sec
 - Damping for primary and secondary systems: $\zeta_p = \zeta_s = 5\%$
 - Parameter $\alpha=0, 5$ and 10




3
4




UB-NCS Testing Protocol

Resulting three dimensional Floor Response Spectra (FRS) for $\alpha=5$ as a function of T_p and T_s




UB-NCS Testing Protocol

84th percentile FRS's and mean 84th percentile FRS along building height



UB-NCS Testing Protocol

Extrapolated mean 84th percentile FRS along building height



$$FRS_{Factor} \left(\frac{h}{H} \right) = 1 + 10 \frac{h}{H} - 19.4 \left(\frac{h}{H} \right)^2 + 12.4 \left(\frac{h}{H} \right)^3$$

$$FRS \left(T, \xi, \frac{h}{H} \right) = FRS_{Factor} \left(\frac{h}{H} \right) S_s \left(T, \xi \right)$$


$$FRS_{Factor} \left(\frac{h}{H} = 0.3 \right) = 2.59$$

37



UB-NCS Testing Protocol

Mean 84th percentile FRS along building height




38



UB-NCS Testing Protocol

Resulting protocol histories ($h/H=0.3$)



$$x_{Bottom}\left(t, \frac{h}{H}\right) = \bar{a} f(t)^\beta \cos(\varphi(t)) w(t) FRS_{Floor}\left(\frac{h}{H}\right)$$


$$x_{Top}\left(t, \frac{h}{H}\right) = x_{Bottom}\left(t, \frac{h}{H}\right) + \Delta\left(t, \frac{h}{H}\right)$$



39

UB-NCS Testing Protocol

Protocol histories ($h/H=0.3$)



Envelope floor motions testing protocol $h/H = 0.3$.

Peak Displacements		Peak Interstory Drift		Peak Velocities		Peak Accelerations	
$D_{Max Bot}$ (in)	$D_{Max Top}$ (in)	Δ_{Max} (in)	δ_{Max} (%)	$V_{Max Bot}$ (in/s)	$V_{Max Top}$ (in/s)	$A_{Max Bot}$ (g)	$A_{Max Top}$ (g)
14.8	16.4	1.65	1.09	21.2	23.2	0.45	0.51



40



Composite Hospital Room Tests

- Demonstrate effects of earthquakes on typical medical equipment and other nonstructural components in hospitals
 - Research emphasis is on partition walls
- Compare loading protocol developed at UB with simulated floor motions
- Verify performance capabilities of UB-NCS with realistic payload




Composite Hospital Room Tests

- Nonstructural components include
 - Steel-stud gypsum partition wall
 - Lay-in suspended ceiling system
 - Fire protection sprinkler piping system
 - Medical gas lines
 - Medical equipment
 - Free-standing
 - Anchored




Partition wall

- Main emphasis of research
- Gypsum panels on steel stud frame
- Layout based on quasi-static test conducted at UC San Diego




Ceiling system

- Suspended ceiling with lay in tiles, including light and sprinkler




Piping System

- Horizontal U-shaped run at top level with single sprinkler head
- Vertical run connecting both levels



Medical Gas Piping System

- Two copper lines connected to wall outlets
- Horizontal run supported by trapeze



Medical Equipment - attached

- Wall mounted monitor
 - Anchored to three stud assembly in wall
 - 4 locations including one faulty installation
- Ceiling mounted surgical lamp
 - Supported by steel frame connected to platform




Medical Equipment – free standing

- Gurney with dummy, IV poles with pumps, Large cabinet on casters with video equip.



Loading Protocol

- Use protocol developed at UB
 - ($h/H=1.0$)
 - Preliminary tests at 10%, 25% and 50% of design level
 - Design Basis Earthquake DBE (100%)
 - Maximum Considered Earthquake MCE (150%)



Peak Displacements		Peak Interstory Drift		Peak Velocities		Peak Accelerations	
$D_{Max Bot}$ (in)	$D_{Max Top}$ (in)	Δ_{Max} (in)	δ_{Max} (%)	$V_{Max Bot}$ (in/s)	$V_{Max Top}$ (in/s)	$A_{Max Bot}$ (g)	$A_{Max Top}$ (g)
16.3	17.6	1.31	0.87	30.5	32.6	0.73	0.77



Simulation using protocol - MCE



Simulation using protocol - MCE



Simulation using protocol - MCE



Simulation using protocol - DBE



Thank you

